BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT16737

MODIFIED APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/09/2014-15, Date: 23.01.2015

Improvemets to and asphalting to roads in DEO Residency layout and surroundings in ward no. 07

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of R SATHEESH	
				In Figures	In Words
1	5854.27	KSRRB M500-6. Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. (P. 157, Item No. 21.6)	Sqm	35.21	Rupees Thirty Five and Twenty One Paise Only
2	29.15	KSRRB M500-18. Providing and laying dense Graded bituminous Macadum using crushed agregates of specified grading premixed with VG30grade bituminous binder and transporting the hot mix to work site , laying to the required grade , level and allignment , rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per morth table 500-10 complete in all respects complete as per specification -do- using 40/60 TPH capacity H.M.P With sensor paver Gr-11 (50mm to 75mm) with 4% VG-30Bitumen pg 159 i.no 21.17.4	cum	9600	#NAME?
3	832.9	KSSRB M500 10 Providing and applying tack coat using 80/100 grade bitumen (VG10) In boiler fitted with spray set distrubuter at the rate of 0.2 kg per sqm on existing prepared bitumenous surface cleaned with mechanical broom complete as per specification pg no : 158 Item no : 21.10	Sqm	14.59	Rupees Fourteen and Fifty Nine Paise Only
4	234.2	KSRRB M500-19. Providing and laying bituminous concrete Using crushed agregate of spacifying grading , premixed with bituminious binder and filler , transporting the hot mx to work site , laying with paver finisher to the required grade , level and allignment , rolling with the smooth wheeled vibrator and tandem rollers to archive the desired compaction as per MORTH specification clause no 509 complete in all respects complete as per specification -do- using 40/60 TPH capacity H.M.P with sensor paver Gr - 1 (50mmto 60mm) with 5.5% CRMB 55 (P.161 item no 21.23.3)	cum	13000	#NAME?
5	166.58	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803 (Page No. 178, Item No. 24.15) SR 2014-15	Sqm	475.2	Rupees Four Hundred Seventy Five and Twenty Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92